

					PROJECT:	TMBNC Building - 804							
					LOCATION:	5938 Julian Airport RD Liberty, NC 27298							
					DATE:	December 20, 2023 - Wednesday							
SR #	CSI SECT	DESCRIPTION	QUANTITY	WASTAGE (10%)	QTY WITH WASTAGE	UNIT OF MEASUREMENT	UNIT LABOR COST	TOTAL LABOR COST	UNIT MATERIAL COST	TOTAL MATERIAL COST	TOTAL ITEM COST	TOTAL TRADE COST	
DIV.01 GENERAL CONDITIONS												\$	-
1		Permit	1	0%	1	LS	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
2		Supervision	1	0%	1	LS	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
3		Final Cleanup	1	0%	1	LS	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
4		Mobilization Cost	1	0%	1	LS	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
5		Projects Overheads	1	0%	1	LS	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
6		Bonds	1	0%	1	LS	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
7		Fees (Architect & Engineer)	1	0%	1	LS	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
8		Temporary Control & Facilities	1	0%	1	LS	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
DIV.04 MASONRY												\$	-
		CMU (Block Wall)											
9		Wall type 04A/08 - 10'-8" H	6612	10%	7,273	SF	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
10		8"x8"x16" CMU blocks	7438	10%	8,182	EA	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
11		#5 bar @ 24" O.C.	3448	15%	3,965	LBS	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
12		Grout filled in CMU wall	81	10%	89	CY	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
13		Sand in CMU wall	26	10%	29	TON'S	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
14		Wall type 04A/08 - 11'-4" H	7561	10%	8,317	SF	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
15		8"x8"x16" CMU blocks	8506	10%	9,357	EA	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
16		#5 bar @ 24" O.C.	3943	15%	4,535	LBS	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
17		Grout filled in CMU wall	93	10%	102	CY	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
18		Sand in CMU wall	30	10%	33	TON'S	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
19		Wall type 04A/08 - 18'-6" H	2803	10%	3,083	SF	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
20		8"x8"x16" CMU blocks	3154	10%	3,469	EA	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
21		#5 bar @48" O.C.	731	15%	841	LBS	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
22		Grout filled in CMU wall	34	10%	38	CY	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
23		Sand in CMU wall	11	10%	12	TON'S	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
24		Wall type 04A/08 -20'-4" H	5072	10%	5,579	SF	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
25		8"x8"x16" CMU blocks	5706	10%	6,277	EA	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
26		#5 bar @48" O.C.	1323	15%	1,521	LBS	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
27		Grout filled in CMU wall	62	10%	68	CY	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
28		Sand in CMU wall	20	10%	22	TON'S	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
29		Wall type 04A/08 -20'-6" H	1051	10%	1,157	SF	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	